

REQUEST FOR PROPOSAL (RFP)

REPAIR, REPLACEMENT, UPGRADE, TESTING AND RECOMMISSIONING OF THE MALL'S ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM

Scope of Work

The Contractor shall conduct a comprehensive assessment of the existing fire detection and alarm system and submit a proposal covering the supply, installation, testing, commissioning, and documentation for the repair and upgrade of the Mall's addressable fire alarm system. The proposal shall include, but not be limited to, the following components:

QTY	DESCRIPTION	REMARK	UNIT PRICE	LINE TOTAL
1	Supply of GENT Addressable 1–4 Loop Vigilon Plus 24 Addressable Fire Alarm Main Panel, including integration with the existing system where applicable.	MAIN PANEL		
385	Replacement/supply and installation of GENT S4 Addressable Smoke Detectors complete with detector bases.	SMOKE		
60	Replacement/supply and installation of GENT S4 VAD Addressable Heat Detectors.	HEAT		
35	Gent S4-34842 Addressable Manual Call Points (MCPs).	MCP		
60	Replacement/supply and installation of GENT S4 Addressable Sounders. Unit	SOUNDER		
20	Supply and installation of GENT Two-Channel Interface Modules. Unit	MODELE		
30	Supply and installation of 1.5mm ² Two-Core Flexible Copper Shielded Fire-Resistant Cables, including termination and testing.	RIM		

1	Provision of all necessary piping, trunking, containment systems, supports and accessories required for cable routing and installation.	LOTS		
4	Supply and installation of GENT Plus Addressable Loop Cards.	CARD		
1	Supply, installation and commissioning of GENT 1–2 Loop Fire Alarm Panel as required for system expansion and integration.	PANEL		
1	Supply and installation of GENT Network Card for inter-panel communication and networking.	CARD		
	All associated civil works, builders' works, installation materials and ancillary accessories necessary for the completion of the project.	LOT		
	Provision of professional services, including system design review, programming, testing, commissioning, as-built documentation, user training, labour and handover.			
			SUBTOTAL	
			VAT	
			TOTAL	

Contractor's Responsibilities

The successful bidder shall:

- Conduct a detailed site survey and verify all quantities before execution.
- Identify defective components within the existing fire alarm system and recommend corrective actions.
- Supply only genuine and approved equipment compatible with the existing GENT Vigilon system.
- Install, configure, program, test and recommission the complete fire detection and alarm system.
- Perform 100% functional testing of all field devices and interfaces.
- Submit test certificates, commissioning reports and as-built drawings upon completion.

- Provide training for the Mall's Operations and Maintenance personnel.
- Provide warranty details for all supplied equipment and workmanship.
- Ensure all works comply with applicable fire safety standards, manufacturer recommendations and statutory requirements.

Commercial Submission

Bidders shall provide a detailed commercial proposal indicating the following:

- Unit Rates;
- Line Item Totals;
- Subtotal;
- Applicable VAT;
- Grand Total;
- Delivery Period;
- Project Execution Timeline;
- Warranty Period;
- Payment Terms;
- Validity of Proposal.

The Contractor shall include any additional items deemed necessary to ensure the complete restoration, reliability and optimal operation of the Mall's Smoke and Fire Alarm System.