



Roundbox Solutions Services

Strategic ICT Consultancy & Solutions

BN:2524839

LAGOS: 13, Oliade Tomori Street, Ikeja, Off Medical Road
IBADAN: 146, Adekunle Fajuyi Road, Opposite Alaafia Hospital, Mokola Ibadan.
IBADAN: 16 & 17, Olushola Shopping Complex, 64 Adekunle Fajuyi Way, Queen's Cinema, Ibadan.
TEL: 0813 474 2330 | 0802 658 5188 | 0703 644 9367
EMAIL: roundboxsolution@gmail.com

Attention: Mr. Terngu Akumeh
Address: Ikeja City Mall, Broll Nigeria

Ref #:RBS-SUPPLY/INSTALLATION2026/07/31

ADDRESSABLE FIRE ALARM SYSTEM

S/N			Description	Qty	Unit Cost (NGN)	Total Cost (NGN)
1	TX7008-6	MAIN PANEL	1.6 loop addressable fire control panel, support up to 1524 devices	1	1,556,339.50	1,556,339.50
2	TX7004	SUB-PANEL	Supply of GENT Addressable 1-4 loop vigilon plus 24 addressable fire alarm main panel, including integration with the existing system where applicable. TANDA Intelligent Fire Alarm Control Panel	1	1,450,140.27	1,450,140.27
3	TX7100	SMOKE	Replacement/supply and installation of GENT S4 Addressable smoke detectors complete with detector bases. TANDA Intelligent Smoke Detector	385	18,489.80	7,118,572.31
4	TX7980	BASE	TANDA Standard base for addressable detectors	385	2,149.34	827,494.25
5	TX7110	HEAT	Replacement/supply and installation of GENT s4 vav addressable heat detectors. TANDA Intelligent Heat Detector	60	17,552.91	1,053,174.50
6	TX7980	BASE	TANDA Standard base for addressable detectors	60	2,149.34	128,960.14
7	TX7140	CALL POINT	Gent S4-34842 addressable manual call point (MCPs) TANDA Intelligent Manual Call Point	35	22,540.47	788,916.43
8	TX7140-MB	BASE	TANDA Mounting Box for TX7140	35	3,664.89	128,271.25
9	TX7300	SOUNDER	Replacement/supply and installation of GENT s4 addressable sounders unit. TANDA Addressable Sounder Strobe	60	27,087.14	1,625,228.46
10	TX7220	MODULE	Supply and installation of GENT two-channels interface modules. TANDA Addressable Dual I/O Module	20	45,136.05	902,721.00
11	RIM	Fire Resistant Cable	Supply and installation of 1.5mm 2 two-core flexible copper shielded fire resistant cables, including termination and testing. (100 meters rim)	30	220,000.00	6,600,000.00
13	LC7004	CARD	Supply and installation of GENT plus addressable loop cards. TANDA Dual Loop Card for extra loops	1	301,099.89	301,099.89
14	TX7002	PANEL	Supply, installation, and commissioning of GENT 1-2 loop fire alarm panel as required for system expansion and integration. TANDA Intelligent Fire Alarm Control Panel	1	879,271.19	879,271.19
15	NC7008-IP	CARD	Supply, installation of GENT network card for inter-panel communication and networking. TANDA NC7008-IP Supports TCP/IP networking	1	104,683.67	104,683.67
16	TX7932	PROGRAMMER	TANDA Handheld Programmer	1	125,460.58	125,460.58
	MATERIAL COST					23,590,333.44
	INSTALLATION COST					7,077,100.03
12	LOTS	PVC	Provision of all necessary piping trunking, containment systems, supports and accessories required for cable routing and installation	1	1,000,000.00	1,000,000.00
17	LOT		All associated civil works, builders' works, installation materials and ancillary accessories necessary for the completion of the project	1	1,000,000.00	1,000,000.00
18	LOT		Provision of professional services, including system design review, programming, testing, commissioning, as-built documentation, user training, labour and handover.	1	1,500,000.00	1,500,000.00
	SUPPLEMENTARY COST					3,500,000.00
	COST BREAK DOWN					
Project Execution Time		3 months	BANK DETAILS			
Warranty Period		3 years on material	FIDELITY BANK		Sub Total	34,167,433.47
Payment Terms		100% material, 50% installation, balance before commissioning	5601495379		VAT @ 5%	2,562,557.51
Validity of Proposal		2 weeks	ROUNDBOX SOLUTIONS SERVICES		Grand Total	36,729,990.98